

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Oakland), Township (Lyon), Corner Code # (G-1), and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Stamp area containing recording fees (\$7.00 MISCELLANEOUS RECORDING, \$2.00 REMONUMENTATION), date (5 JAN 99 8:28 A.M.), receipt number (8A), and approval signature (12-21-98 JS).

I, Randy Kolehouse, in a field survey on October 29, 1998, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns for Corner Code (G-1), Year (1816-1996), Name (Holmes, Alix, Kostecke, Soderberg, Ward, King, N/A), Description (G.L.O., Ashland Gardens L. 107 P. 35, Cert. Survey L. 6586 P. 288, L.C.R.C. L. 11141 P. 620, L.C.R.C. L. 8426 P. 435, L.C.R.C. L. 15772 P. 368) (G-13 T2N R7E), Cert. Survey, O.C. Tax Maps), and Monument Type (Set Post, N/A, 1" Pipe, 3/4" Pinch Pipe, Iron Rod with Brass Cap in Mon. Box, 3/4" Pinch Pipe, N/A).

Records indicate this corner is not common with G-13, T2N, R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found 3/4" pipe 1' ± South of an old fence line running West. Found pipe is 245.56' West of Section 34 which checks distance measurement shown in L.C.R.C. L. 15772 P. 368. The found 3/4" iron is 1.0' North of the Township line. The found 3/4" iron checks surveys and L.C.R.C.'s from 1983 to the present and also checks the following witnesses.

L.C.R.C. L. 8426 P. 435 (1983) West 18.70' PK 30" Oak (m. 18.40') L.C.R.C. L. 11141 P. 620 (1987) W 18.71' to 30" Oak w/PK Nail S Face (m. 18.40')

Measure South 3314.73' to G-2 (G.L.O. = 3319.14') (King Survey (1996) = 3314.73')

Measure East 2658.95' to H-1

Measure West 2584.75' to F-1

Measure East 245.56' to G-13, T2N, R7E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Set a 4" x 36" concrete monument with brass cap stamped "Oakland County Remonumentation P.S. #25854" on the Township line.

- PK Nail & Oakland Co. Remonumentation Tag in N Side 10" Elm S 80° E 47.83'
PK Nail & Oakland Co. Remonumentation Tag in S Side 8" Oak N 87° E 24.92'
PK Nail & Oakland Co. Remonumentation Tag in S Side 34" Oak N 88° W 18.44'
PK Nail & Oakland Co. Remonumentation Tag in S Side P. Pole N 90° W 67.12'
Fence Cor. S 45° E 8.61'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/28/98
EARTH TECH

Surveyor's Michigan License No. 25854

