

LIBER 19296 PG 629

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for County (Oakland), Township (Lyon), Corner Code # (K-8), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, and Private Claims.

Stamp area containing recording fees: \$ 7.00 MISCELLANEOUS RECORDING, \$ 2.00 REMONUMENTATION, date 17 DEC 98 3:40 P.M., and signature G. WILLIAM CADDELL.

Vertical stamp: DE 17 98 3 63 734

Grid table with columns A-M and rows 2-13, used for recording corner locations.

I, Bruce Antcliff, in a field survey on October 26 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table listing corner K-8 with details: 1816 Holmes G.L.O. Set Post, 1989 Boss Cert. Survey L. 11099 P. 695-697 1/2" Iron Rod, 1989 Boss Cert. Survey L. 11156 P. 253-255 1/2" Iron, N/A N/A O.C. Tax Maps N/A.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found a 1/2" iron rod 16.5' ± West of a fence line and tree row running North and South on line of a tree row running East. (Also found a 1/2" iron 16.4' East as shown in Boss Surveys (1989) L. 11099 P. 695 and L. 11156 P. 253.) The found 1/2" iron rod checks cert. surveys from 1989 to the present. Also checks the following witnesses:

- Cert. Survey (1989)
East 16.6' 1/2" Iron (m. 16.4')
N 60° E 39.58' N&T W/S 18" Tree (m. 39.54')
N 05° E 23.85' N&T E/S 6" Tree (m. 23.81')

Measure North 2596.3' to K-7 (G.L.O. = 2640.0') (O.C. Tax Maps = 2605.44')
Measure South 2624.2' to K-9 (G.L.O. = 2640.0') (O.C. Tax Maps = 2623.66') (Boss Eng. = 2624.40')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Replaced 1/2" iron rod with a 4" x 36" concrete monument with brass cap stamped "Oakland County Remonumentation P.S. #25826."
1/2" Iron East 16.4'
PK Nail & Oakland Co. Remonumentation Tag in W Side 20" Oak N 60° E 56.55'
PK Nail & Oakland Co. Remonumentation Tag in E Side 8" Elm N 5° E 23.81'
PK Nail & Oakland Co. Remonumentation Tag in N Side 8" Elm N 90° E 7.24'
PK Nail & Oakland Co. Remonumentation Tag in NE Side 15" Oak S 75° E 39.73'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-10-98
EARTH TECH

Surveyor's Michigan License No. 25826

