

COPY

LIBER 16874PG179

JAN 397001325

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
3 JAN 97 7:55 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county) Located In: Corner Code #
1. Public Land Survey T1N R8E A-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-4-96 TS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak in a field survey on November 26, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (2,2) contains a small circle.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post 1816 G.L.O Survey L.C.R.C. L.6107 P.43 Hubbell 1973 Found "T" iron Subsequent survey indicates point used is same point previously used by others. No witness.

No witnesses were set. L.C.R.C. L.11041 P.608 Higgins 1988 found "T" iron W1/4 Section 6. Set tag w/nail S. face 8" Oak N 10° E 13.88' Set tag w/nail S.E. face 10" Oak N 23° E 39.14' Set tag w/nail N. Face 10" Cherry S. 40° E 6.59' Found "T" iron E 1/4 corner Sec. 1 T.1N. R7E S59.62' Set tag w/nail S.E. face 8" Elm S 56° W 10.72'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered "T" iron w/metal tag RLS #8897 (open field).

SURVEY & REMONUMENTATION

Recovered witnesses:

N 15° E 13.73' found nail w/tag in S. side 10" Oak RLS #12022 S 10° W 59.69 found "T" iron E 1/4 Corner Sec. 1 T.1N. R.7E

MAY 22 1997

COMMISSION

750 FILE 200

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument w/Oakland County Remonumentation Brass Cap.

Witnesses Set:

N 36° E 39.04' nail w/remon cap S.E. side 18" Oak. S 24° W 19.61' nail w/remon cap N.W. side 10" Elm. S 46° E 36.71' nail w/remon cap W. side 14" Oak. N 90° E 6.48' nail w/remon cap N. side 12" Cherry. South 59.69' "T" iron E. 1/4 corner Section 1 T.1N. R.7E.



Signed by Joseph C. Kapelczak Date 12/3/96
Surveyor's Michigan License No. 24598