

**COPY**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>8E</u>	<u>A-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED  
**\$ 7.00 MISCELLANEOUS RECORDING**  
**3 JAN 97 7:54 A.M. RECEIPT# 88**  
**PAID RECORDED - OAKLAND COUNTY**  
**LYNN D. ALLEN, CLERK/REGISTER OF DEEDS**  
**\$ 2.00 REMONUMENTATION**

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 12-9-96 RS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on November 26, 1996 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post 1816 G.L.O. Survey  
 L.C.R.C. L10041 P546  
 Butterfield 1987 cut down 8" tree found 5/8" iron  
 South 2.10' 16 Penny Nail in 6" Elm.  
 N 40° W 34.02' PK nail in root 36" Maple.  
 S 68° W 17.88' nail w/washer in 20" Maple.  
 N 74° W 33.06' PK nail north side 26" Maple.

No witnesses.

**SURVEY & REMONUMENTATION**

MAY 22 1997

COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" iron rod in tree stump.

East 2.06' 16 Penny Nail in west side 8" stump.  
 S 20° W 25.45' 16 Penny Nail in northwest side 8" Elm.  
 N 40° W 34.00' PK nail in northeast leg of Twin 36" stump.  
 N 75° W 33.09' nail in north side of 24" tree stump.  
 S 65° W 17.84' nail w/ washer in north side of Twin 24" Maple.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap on 5/8" rered in tree stump.

Witnesses set.

Set nail w/remon tag in northwest side 8" Elm. S 20 W 25.41'  
 Set nail w/remon tag in north side 24" Twin Maples. 65 W 17.82'  
 Set nail w/remon tag in northeast side 36" tree stump. N. 40 W 34.04'  
 Set nail w/remon tag in northeast side 10" Walnut S 37 E 70.69'



Signed by Joseph C. Kapelczak

Date 12/16/96

Surveyor's Michigan License No. 24598

*7.00 File*