

# COPY

LIBER 16874 PG 175

JAN 397001321

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                |               |
|---------------------------------------|----------------|---------------|
| <u>Oakland</u><br>(county)            | Located In:    | Corner Code # |
| 1. Public Land Survey                 | T1N R8E        | A-6           |
|                                       | T___ R___      | _____         |
|                                       | T___ R___      | _____         |
|                                       | T___ R___      | _____         |
| 2. Property Controlling<br>in Section | S___ T___ R___ | _____         |
|                                       | S___ T___ R___ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S___ T___ R___ | _____         |
|                                       | S___ T___ R___ | _____         |

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 3 JAN 97 7:54 A.M. RECEIPT# 88  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 12-9-96 TS  
 OAKLAND COUNTY REMONUMENTATION  
 GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on November 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 16 | 17 | 18 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey. S 57½° W 9" Maple  
 N 63° W 4" Linwood

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered P.K. nail in bituminous roadway

Recovered witnesses:

N 51° E 38.09' bituminous nail in west side 40" Maple.  
 S 18° E 94.63' P.K. nail in southwest side power pole.  
 S 68° W 28.00' P.K. nail w/washer #24598 in north side Twin 12" tree.

SURVEY &  
 REMONUMENTATION

MAY 22 1997

COMMISSION

700 FILE  
 L.W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod with Oakland County Remonumentation Brass Cap in monument box.

Witnesses Set:

N 51° E 38.09' set nail in west side 40" Maple.  
 S 18° E 94.45' set nail in southwest side power pole.  
 S 68° W 27.99' set nail in north side Twin 12" tree.  
 S 87° E 32.56' set nail in north side 14" Elm



Signed by Joseph C. Kapelczak

Date 12/16/96

Surveyor's Michigan License No. 24598