

COPY

LIBER 16850PG406

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Oakland (county), Located In, Corner Code #. Row 1: Public Land Survey, T1N R8E, A-13. Row 2: Property Controlling in Section, S T R. Row 3: Miscellaneous Property in Sec., S T R.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 DEC 96 10:59 A.M. RECEIPT# 178
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-11-96
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on March 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. survey: N 39 E 20lks, 18" Oak, N 50 W 20lks, 12" Red Oak

No LCRC's.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered witnesses:

- N 42 W 47.47' fd. PK nail w/washer southeast face power pole
N 25 W 47.85' fd. PK nail w/washer east face 24" Ash
N 67 E 81.43 fd. PK nail northwest face power pole
S 26 W 57.32' fd. PK nail w/washer northwest face 12" Ash

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

7.00 FILE
2.00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set O.C. remonumentation brass cap on existing 1" Iron Pipe.

- N 25 W 47.86' set nail w/remon tag in east face 24" Ash
N 68 E 81.71' set nail w/remon tag south side power pole
S 26 E 66.32' set nail w/remon tag west side MBT pole
S 26 W 57.31' set nail w/remon tag in northwest face 12" Ash



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 8/18/96