

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
3 JAN 97 7:53 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R8E	B-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1993
APPROVED ON: 12-9-96 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on November 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey. N 1 1/2° W. 10 lks 10" Beech. S. 7 1/2° E. 30 lks 10" Beech.
There are no L.C.R.C.'s recorded at this time.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" iron rod.

Recovered Witnesses:

N 05° W. 26.05' PK nail E. side 4" twin Elm.
N 05° E. 114.60' PK nail in W. side 6" Cottonwood.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap.

Witnesses Set:

North 95.74' nail w/remon tag E. side 24" Ash.
N 05° W. 26.05' nail w/remon tag in E. side 4" twin Elms.
S 80° E. 79.37' nail w/remon tag in S.W. side twin 6" Box Elders.
S 55° E. 114.60' nail w/remon tag in W. side 6" Cottonwood.

Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/16/96

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

7.00 FILE
2.00

