

**COPY**

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING  
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

3 JAN 97 7:56 A.M. RECEIPT BY  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R 8E	B-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 7-31-96 TMS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on 7 February, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. survey: N 04 W 4lks, 24" Lynn; N 18 W 20lks, 4" Ironwood.

No LCRC's recorded.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered: 1" pipe in monument box 2.00' south of centerline 10 Mile.

Recovered witnesses:

- S 16 E 50.35' Chiseled cross on north rim telephone manhole
- S 26 W 35.23' PK/washer # 24598 in east side telephone pole
- S 26 W 35.46' PK nail in west side telephone pole
- S 68 W 110.28' PK/washer in northwest side 18" Apple

SURVEY &  
REMONUMENTATION

MAY 22 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rod with O.C. remonumentation brass cap.

- S 26 W 35.22' PK/remon tag in east side telephone pole
- S 68 W 110.24' PK/remon tag in northwest side 18" Apple
- N 82 E 158.31' PK/remon tag in east side power pole
- N 05 E 31.92' PK/remon tag in south side power pole
- N 77 W 175.81' PK/remon tag in south side power pole



7.00  
2.00 BMT  
File

Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 7/16/96