

**COPY**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
1. Public Land Survey	T1N R 8E	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 3 JAN 97 7:53 A.M. RECEIPT# 88  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 7-31-96 TMS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on 7 February, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Post set in 1816 G.L.O. survey: S 03 E 16lks, 24" Red Oak; N 82 W 17lks, 9" Aspen.
- LCRC L7716 P 205 LCRC L11545 P142
- Anderson, 1980, 1/2" iron Milletics, 1988, Fd. iron in mon. box
- N 20 E 35.58' Nail east side power pole \* North 33.00' Iron DWR #19005 RLS
- S 05 W 33.28' Nail east side power pole \*N 20 E 35.72' PK #24598 west side utility pole
- \*N 60 W 79.50' Nail west side power pole South 32.95' PK #24598 east side utility pole
- \*N 60 W 79.43' PK #24598 southwest side utility pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Recovered: 1/2" rerod in monument box on centerline 10 Mile Rd.
- Recovered witnesses: \*North 32.97' Fd. 1/2" rerod cap #19005
- N 28 E 35.78' PK west side power pole
- N 73 E 92.75' PK south side power pole
- N 72 E 92.55' Nail northwest side power pole
- \*N 63 W 79.43' PK/tag #24598 south side power pole
- N 63 W 79.48' Nail tag #5390 south side power pole
- S 07 W 32.93' Nail tag #5390 east side utility pole
- S 07 W 33.21' PK/tag #24598 east side utility pole
- S 07 W 33.02' Nail east side utility pole
- \*N 28 E 35.68' PK/tag #24598 west side power pole

**SURVEY &  
 REMONUMENTATION**  
 MAY 22 1997  
 COMMISSION

\* confirms LCRC witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set O.C. remonumentation brass cap on existing 1/2" rerod.
- N 06 E 52.41' PK/remon tag in west side power pole
- S 07 W 33.03' PK/remon tag in east side telephone pole
- N 39 E 86.25' PK/remon tag in west 8" Maple
- S 48 W 84.79' PK/remon tag in northwest side 10" Poplar

700  
2.0  
Feb

Signed by Joseph C. Kapelczak  
 Surveyor's Michigan License No. 24598

Date 7/12/96

