

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R8E	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 19 DEC 96 11:01 A.M. RECEIPT# 178  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1979  
 APPROVED ON: 9-11-96  
 OAKLAND COUNTY RECONSTRUCTION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on February 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. survey: S 74-1/2 E 6lks, 5" Beech, N 68 W 20lks, 6" Lym.

No LCRC's.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1" pipe in Monument Box.

Recovered witnesses:

N 78 W 33.80' PK nail w/tag #12384 N side power pole  
N 02 W 321.39' 1" pipe northeast corner parcel 22-08-200-023

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation brass cap.

N 80 W 33.78' set nail w/remon tag south side power pole  
N 06 W 196.91' set nail w/remon tag east side power pole  
N 59 E 75.62' PK nail w/ remon tag west end top of block sign  
S 62 E 62.51' tip of arrow on hydrant  
S 66 E 71.65' Chisled "+" top of concrete light pole north side

SURVEY &  
 REMONUMENTATION  
 MAY 22 1997  
 COMMISSION

700 FILE  
200



Signed by Joseph C. Kapelczak  
 Surveyor's Michigan License No. 24598

Date 8/8/96