

Dec 1996 306309

LIBER 168500417  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R8E	E-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
19 DEC 96 11:02 A.M. RECEIPT# 17B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1999

APPROVED ON: 9-11-96  
OAKLAND COUNTY REMONUMENTATION  
FREE GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on February 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. survey: S 13 W 36 lks 10" Beech S84 36 lks 12" Sugar Maple.

No LCRC's.

E-5 Witness 1/4" re-rod.

N 60 E 50.76' Pk nail NW side 18" Maple  
N 70 E 55.11' double headed nail w/washer SE side MBT pole  
N 30 W 41.67' nail w/o.cc. washer W side light pole  
N 10 W 85.20' PK nail E side MBT pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/4" re-rod in Monument Box.

Recovered witnesses:

N 37 W 41.61' nail w/washer O.C.R.C. SW MBT pole  
N 37 W 41.75' PK nail SW side MBT pole  
N 20 W 67.77' SE fence corner parcel #22-08-426-019  
N 13 W 85.11' PK nail East side MBT pole  
N 13 W 85.45' PK nail w/shiner NE side MBT pole  
N 59 E 55.10 nail w/tag O.C.R.C. SE side MBT pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation brass cap.

N 37 W 41.72' set nail w/remon tag SW side MBT pole  
N 38 W 64.68' Chisled cross top 36" R.C.P.  
N 13 W 85.46' set nail w/ remon tag NE side MBT pole  
N 59 E 55.04 set nail w/remon tag SE side MBT pole

SURVEY &  
REMONUMENTATION

MAY 22 1997

COMMISSIONER

700 FILE  
200



Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 9/10/96