

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Oakland (county), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 2:02 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-12-95 Tmc/S
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Post set 1816 G.O.L. survey; N 78 W 6lks, 3" Beech; N 63 E 10lks, 4" Beech.
LCRC L6028 P639
Fouty 1972
Fd. 1" pipe centerline Taft Rd
East 51.75' Nail & flag south side power pole
West 51.90' Nail & flag south side power pole
NE 47.76' Nail & flag west side 12" stump

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Recovered 1/2" rerod cap #24598 in monument box on centerline Taft rd
Rrecovered witnesses:
N 88 W 51.59' Nail south side power pole
S 33 E 81.32' PK nail northeast side power pole
S 87 E 52.08' PK nail north side telephone pole
N 08 W 205.21' PK nail east side power pole
S 26 W 159.40' Found 1/2" rerod

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" rerod with O.C. remonumentation brass cap replacing 1/2"rerod
East 52.15' PK/remon tag north side power pole
S 33 E 81.51' PK/remon tag northeast side telephone pole
West 52.21' PK/remon tag south side power pole
N 08 W 205.31' PK/remon tag east side power pole

Grid table with columns A-L and rows 2-13, containing numbers 1-36.



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 6/28/95