

NUMBER **15528** of **768**
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N R <u>8</u> E	<u>H-11</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

\$ 2.00 REMONUMENTATION
19 JUL 95 2:03 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 7-12-95 Toms
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 2, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.O.L. survey; S 89 W 47lks, 10" elm;	S 35 1/2 E 23lks, 10" beech.
LCRC L 7494 P 77	LCRC L 8335 P 569
Anderson 1979	Kapelczak 1982
Fd 1/2" reroed	Fd 1/2" reroed
N 50 W 49.60' Pk nail s.west side 15" twin walnut	N 15 E 44.76' Nail & cap west side 6' elm
S 40 W 68.58' Pk nail in side power pole	S 45 W 68.17' Chiseled cross north rim MBT manhole
S 25 E 84.14' Tip of arrow on fire hydrant	N 30 W 64.69' Nail & cap west side 5" ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" reroed cap #24598 in monument box at 9 mile & Center St.
Recovered witnesses:
S 40 W 84.25' Pk nail north side power pole
S 15 E 68.70' Tip of arrow of hydrant
North 59.75' 1/2" Reroed in concrete monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" reroed with O.C. remonumentation brass cap replacing 1/2" reroed
N 15 W 57.70' Pk/remon tag east side 12" dia. elm
N 10 W 31.00' Pk/remon tag east side 14" dia. elm
N 05 E 61.30' Pk/remon tag west side 12" dia. walnut
S 40 W 68.92' Pk/remon tag southeast side power pole



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 6/28/95

7-26-95