

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Oakland (county), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
3 JAN 97 7:56 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-31-96 TMS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak in a field survey on 29 January, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column I and row 6.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. survey: N 04 W 17lks, 14" Beech; S 34 E 18lks, 8" Sugar.
LCRC L6541 P617 LCRC L6854 P139
Hooth 1975 Fd. 3/8" rerod McMahan, 1977, Fd. handhole
N 55 E 72.96' North bolt on light pole base West 38.00' Nail/cap in wood pole
S 80 E 49.61' Power pole East 49.83' Nail/cap in wood pole
S 25 W 117.09' Telephone pole Northeast 67.00' Bolt in Mobil sign
West 37.87' Telephone pole

LCRC L9149 P475
Ward, 1985, Found iron in mon. box as recorded in Liber 6854 Page 139

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rerod in monument box on centerline Novi Rd.
Recovered witnesses:
S 17 E 202.02' Chiseled cross northeast bolt light pole base
S 18 W 192.21' Chiseled cross northeast bolt light pole base
N 87 W 55.82' Chiseled cross northeast bolt light pole base
N 29 W 123.53' Chiseled cross southeast bolt guy pole base for signal pole

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of this corner:

Set O.C. remonumentation brass cap on existing 1/2" rerod.
S 17 E 202.02' Chiseled cross on northeast bolt light pole base
S 18 W 192.21' Chiseled cross on northeast bolt light pole base
N 87 W 55.82' Chiseled cross on northeast bolt light pole base
N 29 W 123.53' Chiseled cross on southeast bolt guy pole base for signal pole



Handwritten notes: 7.00, 2.00 R, file

Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 7/12/96