

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R8E	J-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
19 JUL 95 2:04 P.M. RECEIPT# 71A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 34S, P.A. 1990  
APPROVED ON: 7-12-95 *Tom S*  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.O.L. survey: S 39 W 13lks, 16" Beech;	N32 W 14lks, 7" Beech.
LCRC L 7716 P 212	LCRC L 11852 P 340
Anderson 1980	Ward 1991
Fd. 1" pipe in mon. box	Fd. 1" pipe in mon. box
N 75 w 94.75' Nail in power pole	N 75 W 94.75' Fd.nail & disc s.west face p.p.
N 07 W 24.60' Nail in power pole	N 07 W 25.60' Fd. nail & disc west face p.p.
N 30 E 72.47' Nail in power pole	N 40 E 72 47' Fd. nail & disc n.west face p.p.
S 36 E 68.45' Nail in 24" dia. Maple	S 36 E 68.45' Fd. nail & disc s.west face 24" Maple

LCRC L 13181 P 699
Kohn 1992
Fd. mon. box
N.west 161.05' Top nut on hyd
*N.east 75.50' Tag #80076 in p.p.
S.east 69.45' Tag #80774 in
22" Maple
S.west 74.10' Top nut on hyd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1" pipe in monument box on centerline 9 Mile Rd.

Recovered witnesses:  
North 59.77' 1/2" rerod cap #21584 (OHM/KSH)  
\*N 45 E 75.45' Nail tag #80776 in power pole

\* confirms LCRC witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C Remonumentation brass cap replacing 1" pipe

N 41 E 75.50' PK/remon tag southeast side telephone pole
S 56 E 66.50' PK/remon tag west side 10" dia. Locust
S 46 E 88.82' PK/remon tag southwest side 10" dia. Pine
S 45 W 73.99' Tip of arrow on Fire Hydrant

Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 6/28/95

