

COPY

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R 8E	K-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 19 DEC 96 11:04 A.M. RECEIPT# 178  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Conformance with  
ACT 74, P.A. 1970

APPROVED ON: 11-6-96  
 GAILLARD COUNTY PERMONUMENTATION  
 FIELD GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on 29 January, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	8	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.L.O. Survey. N 74 W 17 lks 18" White Oak.

S 53 E 32 lks 10" Linwood

L.C.R.C. Pawlarczyk 1976 L.6620 P.276

Found 1-1/2" iron pipe

N.W. 58.08' M.D.O.T. tag in 18" tree

N.N.E. 30.73' M.D.O.T. tag in utility pole

S.E. 32.85' M.D.O.T. tag in utility pole

L.C.R.C. Kapelczak 1982 L.8335 P.571

Set 1/2" rerod in monument box (new road construction)

Set tacked hubs N 20 W 50', 75' and 100'

Set tacked hubs N 45 W 60', 100' and 145'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rerod in monument box centerline Bit. Rd. intersection

Recovered witnesses

N 12 E 38.77' nail w/M.D.O.T. tag east side power pole

N 11 E 38.84' nail w/shiner west side power pole

N 70 W 199.65' 1/2" rerod cap #T. Leiber 274.66' southwest corner Parcel #22-02-400-005

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Brass Cap.

S 68 W 117.62' nail w/remon tag southeast side power pole

S 56 E 72.16' nail w/remon tag southwest side power pole

N 11 E 38.85' nail w/remon tag west side power pole

N 72 W 202.02' nail w/remon tag south side 8" Elm

SURVEY &  
REMONUMENTATION

MAY 22 1997

COMMISSION



Signed by Joseph C. Kapelczak

Date 11/6/96

Surveyor's Michigan License No. 24598