

JUL 19 95 12 9 16 4

LIBER 15528 pg 784

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Oakland (county), Located In: (T1N, R8E, L-9), Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 2:05 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-12-95 [Signature]
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.O.L. survey: S 63 W 10lks, 6" Ironwood, S 68 W 10lks, 11" Beech.
LCRC L 5972 P 20 LCRC L 7300 P 648
Carlson 1972 Stonerock 1978
Found 1/2" rerod Found 1/2" rerod
N 64 W 121.20' PK nail in utility pole N 64 W 121.20' PK nail in utility pole
N 02 E 56.95' PK nail in utility pole N 02 E 56.95' PK nail in utility pole
S 07 W 23.70' PK nail in utility pole S 07 W 23.70' PK nail in utility pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered PK nail 1.50' south of centerline of 10 Mile Rd.

Recovered witnesses:

N 60 W 121.81' PK tag #10705 south side power pole
N 60 W 121.99' Nail tag #OCRC south side power pole
N 05 E 57.58' PK tag #10705 west side power pole
N 05 E 57.81' PK w/bottle cap west side power pole
N 05 E 57.74' Nail tag #MDSH west side power pole
N 05 E 57.90' Nail tag #MDSH west side power pole
S 87 W 189.77' PK nail west side guy pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C. Remonumentation brass cap along with monument box replacing PK nail.

N 60 W 121.83' PK/remon tag southside power pole
N 25 E 87.22' PK/remon tag northwest side 16" dia. Apple
N 07 E 59.32' PK/remon tag west side power pole
S 04 W 79.31' PK/remon tag west side power pole

Grid table with columns A-L and rows 2-13. A dot is present at row 9, column K.

Signed by [Signature]
Surveyor's Michigan License No. 24598

Date 6/28/95

