

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Oakland (county), Located In, Corner Code #, and numbered sections 1-3 for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 2:06 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-12-95 Tomco
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on March 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1815 G.O.L. survey by Alexander Holmes (Michigan baseline): S 78 E 4lks, 6" Sugar, N 43 W 31lks, 9" Sugar.

NO LCRCs recorded.

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rerod in concrete monument in monument box on centerline 8 Mile Rd.

Recovered witnesses:

- List of recovered witnesses including bearings and distances: N 38 E 71.81' 1/2" rerod cap #26459, N 44 W 84.31' PK tag #WCR s.west side 8" Ash, etc.

- List of recovered witnesses including bearings and distances: S 40 W 54.57' Nail tag #MSHD west side 12" Elm, S 61 W 83.22' PK tag #WCR s.east side 10" Elm, etc.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C. Remonumentation brass cap replacing 1/2" rerod & concrete monument.

- List of monument descriptions: N 44 W 84.04' PK/remon tag northeast side 8" dia. Ash, S 06 E 56.30' PK/remon tag east power pole, etc.

Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 6/28/95

