

LIBER 168500438

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Oakland), Located In, Corner Code #, and sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Dec 1996 3063
\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 DEC 96 11:05 A.M. RECEIPT# 178
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Register of Deeds Stamp & File Number
APPROVED BY 11-6-96
MICHIGAN COUNTY REMONUMENTATION
TELE GROUP COMMITTEE

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on September 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A through L and rows 2 through 13, containing numbers 1 through 36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of monuments including: Post set in 1816 G.L.O. Survey, L.C.R.C. L.6405 P.378 Stonerock, 1974; L.C.R.C. L.11041 P.609 Higgins, 1988; L.C.R.C. L.10966 P.427 Schultz, 1989; L.C.R.C. L.6107 P.39 Hubbell, 1973.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- List of corner evidence including: Recovered 1/2" rerod w/cap MDOT #31610 in monument box in Bit. Road 1.0' (+/-), west centerline Haggerty Road; N 36 W 59.96' nail w/tag M.S.H.D. southwest side power pole; N 35 W 59.89' nail w/tag G.W. 22445 northeast side power pole; S 25 W 99.17' nail w/tag G.W. 22445 east side power pole; S 25 W 99.16' nail w/M.S.D.H. tag northwest side power pole; N 41 E 34.86' nail w/tag G.W. 22445 top of guard rail; S 80 E 24.76' nail w/tag G.W. 22445 top of guard rail.

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- List of monuments including: Set remonumentation brass cap; N 36 W 59.80' set nail w/remon tag southwest side power pole; S 25 W 99.41' set nail w/remon tag east side power pole; S 80 E 24.96' set nail w/remon tag top of guard rail; S 76 E 81.52' set nail w/remon tag south side 14" Walnut.



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 11/6/96