

LIBER 16850 PG 441

NOTE COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (county)	Located In:	Corner Code #
1. Public Land Survey	T1N R8E	M-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 19 DEC 96 11:05 A.M. RECEIPT# 178
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

APPROVED ON 11-6-96
 OAKLAND COUNTY REGISTER OF DEEDS
 FILE GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on September 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	16	17	18	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Post set in 1816 G.L.O. Survey. N 47-1/2 W 43 lks, 14" Sugar Maple, N 39-1/2 W 28 lks 8" Ironwood
- L.C.R.C. Moran, 1989 L.11057 P.821
- Copper clad rod in monument box
- S 47 E 73.59' nail and tag in power pole and telephone pole
- S 54 W 80.00' PK nail in power pole and telephone pole
- N 40 W 74.87' southeast stud in traffic pole
- N 71 E 90.57' nail and tag in telephone pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" iron rod in monument box in concrete road.
 No witnesses.

SURVEY &
 REMONUMENTATION

MAY 22 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation brass cap.

- S 36 W 121.74' chisled "+" north rim g.v. and well
- N 86 W 50.10' chisled "+" east side light pole base
- N 89 W 41.53' chisled "+" north rim storm manhole
- S 86 E 50.81 chisled "+" west side light pole base



Signed by Joseph C. Kapelczak
 Surveyors Michigan License No. 24598

Date 11/6/96