

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION
19 JUL 95 2:06 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Table with columns: Oakland (county), Located In:, Corner Code #. Rows include Public Land Survey (T1N R8E M-11), Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-12-95 TWO
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1816 G.O.L. survey: N 53 1/2 W 20lks, 6" Ironwood; S 57 W 29lks, 7" Ironwood

LCRC L 5871 P 889
Jones 1972 Found 1/2" pipe
S 30 E 81.47' 17" Walnut
S 36 W 36.95' 17" Walnut
N 38 W 76.51' 22" Hickory

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" rerod in monument box on centerline Haggerty Rd. & 12.75' south of centerline 9 Mile Rd.

Recovered witnesses:

S 55 E 59.66' Nail w/washer northeast side guy pole
S 54 E 59.54' PK nail w/washer southwest side guy pole
S 50 W 51.52' Chiseled cross on top of curb

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C. Remonumentation brass cap replacing 5/8" rerod

N 41 E 105.14' PK/remon tag southeast side power pole
S 54 E 59 57' PK/remon tag southwest side guy pole
N 69 W 190.18' PK/remon tag northeast side power pole w/transformer
N 38 W 93.11' PK/remon tag northeast side power pole



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 6/28/95