

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JA-298000208

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E A-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

SURVEY &
REMONUMENTATION
MAR 21 2000

Compliance with
 \$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 \$ 0.00 COUNTY REMONUMENTATION
 PAID PEER GROUP COMMITTEE
 LYNN M. ALLEN, CLERK REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817 Post	S. Carpenter	n/a	GLO notes
1989 1" Bolt	R. Roon	#13593	L.C.R.C. L11057, P818
1989 1" Square bar in mon box	R. Donnelly	#21563	L.C.R.C. L11062, P207

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1" square bolt in monument box currently occupies this corner. The following witness ties were used to recover and verify its position. All four witness ties from the above mentioned L.C.R.C's match current measurements. Field measurements were made between the following corners:

A-8 to A-7	A-7 to B-7	A-7 to M-7 (T-1-N, R-8-E)
2646.07 meas.	2525.76 meas.	44.16 meas.
G.L.O. not applicable	2508.66 G.L.O.	3.18' G.L.O.
2646.22 M.D.O.T.		44.22 Rec. L.C.R.C. L11062, P207
		44.25 Rec. M.D.O.T. ROW plans

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" square iron with a 5/8" x 24" iron rod with 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281". Witnesses are as follows:

N. 41° E., 32.11'	Set P.K. and remon. washer top guard rail post
S. 19° E., 73.59'	Set P.K. and remon. washer top guard rail post
S. 12° W., 75.66'	Set P.K. and remon. washer top guard rail post
N. 37° W., 32.73'	Set P.K. and remon. washer top guard rail post
Due South, 44.16'	1" square bolt in mon box M-7 (T-1-N., R-8-E.)



700 FILE
200

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date April 24, 1997
 Surveyor's Michigan License No. 37281