

LIBER 17932 PG 761

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E A-8
2. Property Controlling in Section S T R SURVEY & REMONUMENTATION
3. Miscellaneous Property in Sec. S T R MAR 21 2000

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 JAN 98 9:00 A.M. RECEIPT# 12A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990
APPROVED ON: 4-28-97 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

JA-2980000209

4. Lot No. , Recorded Plat SECTION
5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (8, A) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

1817 Not set S. Carpenter N/A G.L.O. notes
1972 3/8" Iron rod P. Wetoskey #2934 L.C.R.C. L5871, P887
1978 5/8" Rod in monument box R. Roon #13593 L.C.R.C. L11057, P818

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron in a monument box currently occupies this corner. The following witness ties were used to recover and verify its position:

One tie matches current measurements from L.C.R.C. L5871, P887
Five ties match current measurements from L.C.R.C. L11057, P818

Field measurements were made between the following corners:

A-8 to A-7 2646.07 meas.
A-8 to M-8 (T-1-N., R-8-E.) 38.35 meas.
A-8 to A-9 2666.83 meas.
G.L.O. not applicable 38.37 Rec L.C.R.C. L11057 P818 G.L.O. not applicable
2646.22 M.D.O.T. ROW plans 38.40 Rec M.D.O.T. ROW plans 2667.21 Rec. M.D.O.T. ROW plans 63-R-1 Sheet 13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" square iron with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped "Oakland County Remonumentation, P.S. #37281". Witnesses are as follows:

N. 20° W., 120.57' Set P.K. nail and remon. washer S.W. face U-pole
S. 30° E., 53.54' Set P.K. nail and remon. washer N.E. face U-pole
N. 22° E., 143.59' Set P.K. nail and remon. washer N. W. face U-pole
S. 55° W., 63.26' Found P.K. nail and remon. washer S.E. face U-pole
Due South 38.35' Found iron with remon. cap in monument box M-8 (T-1-N., R-8-E.)

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date April 24, 1997



700 FILE