

LIBER 15528 PC 760

JUL 1995 12914

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (county) Located In: Corner Code #
1. Public Land Survey T1N R9E A-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 2:02 P.M. RECEIPT# 71A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 7-12-95 Tms
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on March 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.O.L. survey.

LCRC L 5871 P 881
Jones 1972 "T" iron
N 41 W 65.37' 22" Oak
S 25 E 93.87' 17" Walnut
S 25 W 46.86' 17" Walnut

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" rerod in monument box at centerline Haggerty & 9 Mile Rds.

Recovered witnesses:

N 45 E 95.75' Nail southeast side power pole
S 46 E 67.68' PK washer 14864 southwest side power pole
S 47 E 67.65' Nail washer northeast side power pole
South 12.58' 5/8" rerod in mon. box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C. Remonumentation brass cap replacing 5/8" rerod

N 45 E 95.75' PK/remon tag southeast side power pole
N 44 W 83.50' PK/remon tag northeast side power pole
N 74 W 186.20' PK/remon tag northeast side power pole
S 46 E 67.71' PK/remon tag southwest side power pole

Signed by

Joseph C. Kapelczak

Date

6/28/95

Surveyor's Michigan License No.

24598

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 in a grid pattern.

7.00
2.00
Pm

