

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

Located In: Farmington Twp. Corner Code #

- 1. Public Land Survey      T 1-N R 9-E      B-7  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
REMONUMENTATION**

**MAR 21 2000**

**SECTION**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

JA-29800002

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 2 JAN 98 9:00 A.M. RECEIPT# 12A  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS  
 ACT 387 P.A. 1990

APPROVED ON: 4-28-97 RS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1817	Set post	S. Carpenter	n/a	GLO notes
1990	1/2" Iron rod with cap #25860 in mon box	T. Moran	#25860	L.C.R.C. L11449, P709

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A 1/2" Iron in monument box 1.0' east of the west edge of metal of east bound I-696 currently occupies this corner. The following ties were used to recover and verify its position. Two current measurements match ties from L.C.R.C. L11449, P709. Field measurements were made between the following corners:

A-7 to B-7	2525.76 meas.	B-7 to C-7	2650.67 meas.
	2508.66 G.L.O.		2640.00 G.L.O.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation P.S. #37281" on the existing 1/2" iron rod in monument box. Witnesses are as follows:

Due West,	87.45'	Set P.K. nail and remon. washer S. face 12" Oak
S. 3° W.,	54.53'	Found cross stamped station 38+00 in pavement
N. 2° W.,	46.17'	Found cross stamped station 39+00 in pavement
Due East,	7.70'	Set P.K. nail and remon. washer in pavement 1.0' West of East E/shoulder



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash  
Surveyor's Michigan License No. 37281

Date April 24, 1997