

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County) Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9 E B-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____ SURVEY &
 3. Miscellaneous S _____ T _____ R _____ REMONUMENTATION
 Property in Sec. S _____ T _____ R _____ MAR 21 2000

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 JAN 98 9:00 A.M. RECEIPT# 12A
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 4-28-97 rs
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, John N. Redash in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9	●											
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817	Set post	S. Carpenter	n/a	G.L.O. Notes
1973	Not described	R. Patterson	#17631	Survey L6213, P402
1983	Not described	J. Kapelczak	#24598	Survey unrecorded
1986	1" Form pin	G. Ward	#22445	L.C.R.C. L9683, P768
1989	Boat spike in monument box	R. Roon	#13593	L.C.R.C. L11057, P818

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A boat spike in monument box currently occupies this corner. Current measurements match 2 ties from L.C.R.C. L9683, P768 and 4 ties from L.C.R.C. L11057, P818. Field measurements were made between the following corners:

B-9 to C-9	A-9 to B-9
2657.00 meas.	2540.60 meas.
2640.00 Rec. G.L.O.	2519.22 Rec. G.L.O.
	2539.95 Rec. Unrecorded Survey #24598
	2539.55 Rec. M.D.O.T. ROW Plans 63-R-1 Sheet 250

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the boat spike with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped "Oakland County Remonumentation PS 37281" in the existing monument box. Witness ties are as follows:

Due North, 51.55	P.K. nail and remon. Washer in East face U-Pole
N 62° E., 56.66	Southwest corner catch basin rim
S 52° E., 56.82	Northwest corner catch basin rim
S 50° W., 61.47	Centerline top nut fire hydrant



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date April 24, 1997