

LIBER 17932PG765

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey	T <u>1-N</u> R <u>9-E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

SURVEY & REMONUMENTATION
MAR 21 2000

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 JAN 98 9:01 A.M. RECEIPT# 12A
PAID **RECORDED** with OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
APPROVED ON: 4-28-97 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

JA-2 98 000021

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6	5		4		3		2		1	
3												
4		7	8		9		10		11		12	
5												
6		18	17		16		15		14		13	
7												
8		19	20		21		22		23		24	
9												
10		30	29		28		27		26		25	
11												
12		31	32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1816 Set post corner J. Wampler n/a GLO notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron in monument box currently occupies this corner. No L.C.R.C's or surveys have been recorded in this 1/4 section. Field measurements were made between the following corners:

B-13 to C-13 2638.02 meas. 2640.00 Rec. G.L.O. 2632.74 Rec. Plates L93, P16, 17 and L102, P5, 6	B-13 to B-1 (T-1-S., R-9-E.) 91.18 meas. 90.93 Rec. Plate L93, P16, 17	A-13 to B-13 2632.68 meas. 2640.00 Rec. G.L.O.
--	--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing 1/2" iron in monument box. Witnesses are as follows:

N. 47° W., 85.69'	P.K. nail and remon. washer S.W. face U-pole
N. 45° E., 82.38'	P.K. nail and remon. washer W. face 12" Spruce
S. 35° E., 116.32'	P.K. nail and remon. washer W. face MBT pole
S. 50° W., 52.75'	N.E. corner catch basin rim
Due West, 91.18'	Found iron in monument box (B-1) T-1-S., R-9-E.



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date April 24, 1997
Surveyor's Michigan License No. 37281

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1988
REVISED MAY 14, 1991
REVISED JAN. 1997
REVISED OCT. 1997