

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E C-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____
 S _____ T _____

3. Miscellaneous Property in Sec. S _____ T _____
 S _____ T _____

SURVEY & REMONUMENTATION
MAR 21 2000

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 JAN 98 9:01 A.M. RECEIPT# 12A
 PAID RECEIVED BY OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEED
 APPROVED ON: 1-20-98
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Numl

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
1										
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 Set Post	S. Carpenter	n/a	G.L.O. Notes
1972 Found 1/2" iron in monument box	E. O'Rourke	#16937	L.C.R.C. L6014 p.621
1973 Found monument box	E. O'Rourke	#16937	Survey L6014 P.618
1974 Found 1/2" iron in monument box	D. Pawlaczyk	#17632	Survey L6274 p.529
1974 Found 1/2" iron in monument box	D. Pawlaczyk	#17632	L.C.R.C. L6266 p.865, 866

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron in monument box currently occupies this corner. 2 current measurements match 2 ties from L.C.R.C. L6014 p.621 and 1 tie from L.C.R.C. L6266 p.865. Field measurements were made between the following corners:

C-7 to C-8	C-8 to C-9
2654.35 meas.	2651.14 meas.
2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.
2654.48 Rec. Survey L6014 p.618	2649.95 Rec. Tax maps
2655.15 plats L165 p.10	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS 37281" on the existing 1/2" iron in monument box. Witness ties are as follows:

N 80° W., 81.58'	P.K. nail and remon. washer	North face 18" Pine
N 45° E., 92.27'	P.K. nail and remon. washer	West face wood fence post
Due East, 56.16'	Found nail and tag #3577	South face U-Pole
S 45° E., 76.98'	Southwest corner brick building	

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date April 24, 1997
 Surveyor's Michigan License No. 37281

