

LIBR 17932PG770

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey

T 1-N R 9-E C-11

T R

T R

T R

2. Property Controlling in Section

S T R SURVEY & REMONUMENTATION

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-28-97 FS OAKLAND COUNTY REMONUMENTATION

\$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION mp & File Number

2 JAN 98 9:02 A.M. RECEIPT# 12A PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

4. Lot No. , Recorded Plat SECTION

5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is present at row 11, column C.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 5 columns: Year, Description, Name, ID#, Notes. Rows include 1817 Set post corner, 1971 Not described, 1972 1/2" Diameter iron bar, 1977 Not described, 1978 Found iron, 1991 Found iron in well.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron in monument box currently occupies this corner. Current measurements match one tie from L.C.R.C. L7000, P840 and four ties from L.C.R.C. L12157, P620. Field measurements were made between the following corners:

Table with 4 columns: Corner pair, Measurement, Rec. G.L.O., Rec. Survey. Rows include C-10 to C-11, B-11 to C-11, C-11 to C-12, C-11 to D-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing 1/2" iron monument box. Witness ties are as follows:

Table with 3 columns: Angle, Distance, Description. Rows include N. 60° W., 49.95' Centerline water gate valve, S. 45° W., 81.00' P.K. nail and remon. washer in E. face U-pole, S. 45° E., 78.22' P.K. nail and remon. washer in W. face U-pole, N. 45° E., 60.91' P.K. nail and remon. washer in N. face U-pole, S. 40° W., 84.87' Found concrete monument.



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash

Date April 24, 1997

Surveyor's Michigan License No. 37281