

LIBER 17932PG771

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Farmington Twp. Corner Code #

- 1. Public Land Survey T 1-N R 9-E C-12
2. Property Controlling in Section S T SURVEY & REMONUMENTATION
3. Miscellaneous Property in Sec. S T R MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-28-97 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

REGISTRATION FEE \$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

2 JAN 98 9:02 A.M. RECEIPT# 12A

PAID B C D RECORDED OAKLAND COUNTY

LYAN D. ALLEN, CLERK/REGISTER OF DEEDS

Grid table with 13 rows and 7 columns, containing numbers 1-36 and a dot in cell 12-32.

SECTION

- 4. Lot No. , Recorded Plat
5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Year, Description, Name, and Notes. Includes entries for 1817, 1978, and 1989.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 5/8" pipe in asphalt pavement 1.5' west of approximate centerline currently occupies this corner. Current measurements match one from L.C.R.C.'s L7157, P647, 648, & L7287, P573, 574. Measurements are inconsistent with L.C.R.C., L11062, P242 which place t corner N. 40° E., 0.98' of aforementioned pipe to a found P.K. nail. The following measurements were obtained between the found P.K. nail and adjoining section corners.

Table with 2 columns: C-11 to C-12 and C-12 to C-13. Lists measurements and recording information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found P.K. nail in asphalt with a 5/8" x 24" iron rod in a new monument box with a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281". Witnesses are as follows:

Table with 3 columns: Angle/Distance, Description, and Witness/Notes. Lists survey measurements and monument details.



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date April 24, 1997
Surveyor's Michigan License No. 37281