

LIBER 17932 PG 772
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E C-13
 T R
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
 REMONUMENTATION**

MAR 21 2000

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 4-28-97 rs
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

JA-298000220

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

\$ 7.00 MISCELLANEOUS RECORDING						
\$ 2.00 REMONUMENTATION						
2 JAN 98	9:02 A.M.	RECEIPT# 12A				
PAID 6	5	RECORDED - OAKLAND COUNTY				
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

A. Description of original monument and accessories and/or subsequent restoration:

1816	Set post corner	J. Wampler	n/a	GLO notes
1989	Found concrete monument in monument box	R. Donnelly	#21563	L.C.R.C. L11062, P242

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod in monument box currently occupies this corner. Current measurements match only one and only accessories remaining from L.C.R.C. L11062, P242. Field measurements were made between the following corners:

C-12 to C-13	C-13 to B-13	C-13 to D-13
2649.52 meas.	2638.02 meas.	2627.00 meas.
2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.
2649.80 Rec. Tax map	2632.74 Rec. Plats, L93, P16, 17 & L102, P5, 6	2632.68 Rec. Plat L53, P48
2649.55 Rec. plat L53, P48		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing 1/2" iron in monument box. Witnesses are as follows:

N. 48° W.,	118.34'	P.K. nail and remon. washer S. face U-pole
N. 25° E.,	56.99'	P.K. nail and remon. washer E. face U-pole
S. 10° E.,	47.42'	P.K. nail and remon. washer W. face U-pole
S. 45° W.,	121.93'	P.K. nail and remon. washer E. face U-pole
Due West,	113.55'	Found iron in monument box (C-1, T-1-S., R-9-E.)



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date April 24, 1997