

COPY

LAND CORNER RECONSTRUCTION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland
(County)

Located in: Farmington Twp. Corner Code #

1. Public Land Survey	T <u>1-N</u> R <u>9-E</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

MAR 21 2000

SECTION

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 JAN 98 9:02 A.M. RECEIPT# 128
 PAID RECORDED IN OAKLAND COUNTY
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS
 APPROVED ON: 4-18-97 rs
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

1816	Set post corner	J. Wampler	n/a	GLO notes
1989	Found concrete monument in monument box	R. Donnelly	#21563	L.C.R.C. L11062, P239
1995	Not described	R. Higgins	#21570	Unrecorded survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A concrete monument in a monument box currently occupies this corner. Current measurements match four ties from L.C.R.C. L11062, P239. Field measurements were made between the following corners:

C-13 to D-13	D-13 to E-13
2627.00 meas.	2627.42 meas.
2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.
2632.68 Rec. Plat L53, P48	2627.74 Rec. #21570

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing monument in monument box. Witnesses are as follows:

N. 70° W., 188.28'	P.K. nail and remon. washer S.face U-pole
N. 10° W., 61.15'	P.K. nail and remon. washer N.E. face light pole
N. 30° E., 57.91'	P.K. nail and remon. washer N.W. face U-pole
S. 80° W., 189.56'	P.K. nail and remon. washer N. face U-pole
S. 20° E., 59.09'	P.K. nail and remon. washer S.E. face U-pole



700 FILL
200

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date April 24, 1997