

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E E-7
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
SECTION

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 JAN 98 9:03 A.M. RECEIPT 12A
PAID RECORDED with OAKLAND COUNTY
LYNN D. ALLEN CLERK/REGISTER OF DEEDS
APPROVED ON: 4-28-97 15
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

JA-298000225

4. Lot No. , Recorded Plat
5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at row 7, column E.

A. Description of original monument and accessories and/or subsequent restoration:

1817 Set post corner S. Carpenter n/a GLO notes
1978 Found 1/2" iron bar, removed and replaced with concrete monument D. Vitins #17324 L.C.R.C. L7112, P798, 799

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A concrete monument 2.5' north of north back of curb of Eleven Mile currently occupies this corner. No current measurements agree with witness ties from L.C.R.C. L7112, P798, 799. Field measurements were made between the following corners:

D-7 to E-7 2633.15 meas.
2615.58 G.L.O.
2634.66 Rec Plats L79, P13 & L83, P38
E-7 to F-7 2640.41 meas.
2635.71 G.L.O.
E-7 to E-8 2643.98 meas.
2640.00 G.L.O.
2644.04 Rec. Plats L180, P27

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I left concrete monument undisturbed. Witnesses are as follows:

S. 5° E., 60.05' Found 1/2" iron
S. 45° E., 59.60' P.K. nail and remon. washer E. face 24" Maple
S. 80° E., 62.32' P.K. nail and remon. washer S. face U-pole
N. 20° W., 20.87' P.K. nail and remon. washer W. face 8" Elm

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available position of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date April 24, 1997



700 FILE