

COPY

LIBER 17932PG779

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located in: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E E-9
T R
T R
T R
2. Property Controlling in Section S T R SURVEY & REMONUMENTATION
S T R
3. Miscellaneous Property in Sec. S T R MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-28-97 rs
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

\$ 7500.00 Miscellaneous Recordation Fee Number

\$ 2.00 REMONUMENTATION
2 JAN 98 9:03 A.M. RECEIPT# 12A
PAID BY C D RECORDED IN OAKLAND COUNTY, MI

LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Grid table with columns 1-6 and rows 1-13. A black dot is located at the intersection of row 9 and column 3.

4. Lot No. , Recorded Plat SECTION
5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Year, Description, Name, License #. Includes entries for 1817 Set post corner, 1972 1/2" iron in monument box, 1973 3/8" steel bar in hand hole, 1973 3/8" rod in monument box, 1973 3/8" rod in hand hole, 1974 Found monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod in monument box currently occupies this corner at the approximate intersection of Drake Road and Grand River. No accessories are remaining of the above listed documents. Field measurements were made between the following corners:

Table with 4 columns: Corner pair, Measurement, Corner pair, Measurement. Includes entries for E-8 to E-9, D-9 to E-9, E-9 to E-10, E-9 to F-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing 1/2" iron rod in monument box. Witnesses are as follows:

Table with 4 columns: Bearing, Distance, Description, Location. Includes entries for N. 44° E., 74.00', P.K. nail and remon. washer N.W. face U-pole.

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date April 24, 1997

