

COPY

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

179321780

For corners in

Oakland

(County)

Located in: Farmington Twp. Corner Code #

1. Public Land Survey

T 1-N R 9-E E-10  
T R SURVEY &  
T R REMONUMENTATION

2. Property Controlling in Section

S T R  
S T R MAR 21 2000

3. Miscellaneous Property in Sec.

S T R  
S T R SECTION

4. Lot No. , Recorded Plat

5. Private Claims

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817	Set post	S. Carpenter	n/a	GLO notes
1972	Found 1/4" R.R.	G. Stonerock	#13601	Survey L6010, P162
1973	Found 1/4" R.R.	G. Stonerock	#13601	L.C.R.C. L6022, P367
1973	Found 1/4" R.R.	G. Stonerock	#13601	Survey L6083, P30
1993	Found R.R. spike	S. Young	#25885	Unrecorded survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found R.R. spike in hand hole at approximate centerline of Drake Road currently occupies this corner. No accessories are existing from above listed documents. The following field measurements were made between the following corners:

E-9 to E-10	2652.15 meas.	E-10 to E-11	2642.41 meas.
2640.00 Rec G.L.O.		2640.00 Rec. G.L.O.	
2649.55 Tax map & Plat L125, P4		2642.46 Unrecorded survey	
		2645.29 M.D.O.T. ROW plans	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the R.R. spike with a 5/8" x 24" iron rod with 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281". Witnesses are as follows:

N. 85° E., 62.46'	P.K. nail and remon. washer S. face 18" Locust
N. 30° W., 95.01'	P.K. nail and remon. washer N.E. face U-pole
N. 60° W., 80.51'	P.K. nail and remon. washer N. face 12" Locust
S. 45° W., 69.24'	P.K. nail and remon. washer N.W. face U-pole

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner

Signed by John N. Redash

Date April 24, 1997

Surveyor's Michigan License No. 37281



Compliance with ACT 345, P.A. 1990  
APPROVED ON: 4-20-97 JS  
OAKLAND COUNTY REMONUMENTATION PEER REVIEW COMMITTEE  
\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
Regis. Section Stamp & File Number  
2 JAN 98 9:03 A.M. RECEIPT# 12A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

JA-298000228

7:00 FILE