

COPY

LIBER 17932 PG 783

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey	T <u>1-N</u>	R <u>9-E</u>	<u>E-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

SURVEY & REMONUMENTATION
MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-28-97 TS
 OAKLAND COUNTY REMONUMENTATION
 \$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 JAN 98 9:04 A.M. REGISTER OF DEEDS STAMP & FILE NUMBER
 RECEIPT # 12A
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816	Set post	J. Wampler	n/a	GLO notes
1949	Not described	L. Fall	n/a	Unrecorded survey
1989	Found concrete monument in monument box	R. Donnelly	#21563	L.C.R.C. L11062, P238
1995	Not described	R. Higgins	#21570	Unrecorded survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron in concrete in an existing monument box currently occupies this corner. The following witness ties were used to recover and verify its position. Four current measurements match ties from L.C.R.C. L11062, P238. Field measurements were made between the following corners:

E-12 to E-13	2640.61 meas.	D-13 to E-13	2627.42 meas.	E-13 to F-13	2535.74 meas.
2640.00 Rec. G.L.O.		2640.00 Rec. G.L.O.		2534.72 Tax maps	
		2627.74 Rec. 1995 Unrecorded survey		2640.00 Rec. G.L.O.	
				2531.82 Rec. 1949 Unrecorded survey	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS#37281" on the existing iron in monument box. Witnesses are as follows:

N. 50° E.,	64.93'	Center of fire hydrant
S. 65° E.,	141.81'	P.K. nail and remon. washer N.E. face U-pole
S. 25° W.,	46.47'	Center of fire hydrant
S. 60° W.,	106.88'	P.K. nail and remon. washer N.W. face U-pole
Due West,	101.42'	Found iron in monument box (E-7, T-1-S., R-9-E.)



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date April 24, 1997

Surveyor's Michigan License No. 37281