

LIBER 17932PG784

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E \_\_\_\_\_ F-7 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY & REMONUMENTATION**  
MAR 21 2000

Compliance with ACT 345, P.A. 1990  
 \$ 7.00 MISCELLANEOUS/RECORDING F'S  
 \$ 2.00 REMONUMENTATION  
 2 JAN 98 \$ 1.00 NONP COMPT FEE  
 PAID Register of Deeds State of Michigan  
 LYNN B. ALLEN, CLERK/REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, John N. Redash, in a field survey on May 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1816 Set post corner J. Wampler N/A G.L.O. notes  
 No L.C.R.C.'s have been recorded as of this date.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field investigation found no corner marker at this position. Three subdivisions are currently occupying the south line of Section 16; "Ramble Hills Subdivision No. 2" L168, P29, 30; "Windwood Pointe Subdivision" L196, P25; and "Normandy Hills No. 1" L72, P40 with various angle points along said line. F-7 was set on the south line of Lot 1 of "Windwood Pointe Subdivision" and midway between the S.W. corner and S.E. corner of said Section 16.

Field measurements were made between the following corners:

E-7 to F-7 2640.50 meas. F-7 to G-7 2640.50 meas.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" X 24" iron rod with 2" diameter brass cap stamped "Oakland County Remonumentation PS#3728" on the south line of "Windwood Pointe Subdivision" L196, P25. Witness ties are as follows:

N. 83° E., 24.20' P.K. nail & remon. tag North face 8" Cherry  
 S. 32° E., 17.54' p.k. nail & remon. tag S.W. face 4, 4, 6, & 14" Elm  
 N. 59° W., 33.13' P.K. nail and remon. tag South face 8" Maple  
 N. 60° E., 63.62' P.K. nail and remon. tag S.E. face 14" Elm



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash  
 Surveyor's Michigan License No. 37281

Date May 24, 1997