

COPY

LIBER 17932PG785

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located in: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E F-9
 T ___ R ___
 T ___ R ___ SURVEY &
 T ___ R ___ REMONUMENTATION
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___ MAR 21 2000
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___ SECTION

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 5-11-97 TJ
 OAKLAND COUNTY REMONUMENTATION
 REEF GROUP COMMITTEE
 \$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REGISTER OF DEEDS STAMP & FILE NUMBER
 2 JAN 98 9:04 A.M. RECEIPT# 12A
 PAID RECORDED - OAKLAND COUNTY
 LYNN B. ALLEN, CLERK/REGISTER OF DEEDS.

JA-2 98 000233

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John N. Redash, in a field survey on April 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1					
2	6	5	4	3	2
3					
4	7	8	9	10	11
5					
6	18	17	16	15	14
7					
8	19	20	21	22	23
9			●		
10	30	29	28	27	26
11					
12	31	32	33	34	35
13					

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 Set post S. Carpenter n/a GLO notes
 1973 Found 1/2" pipe N. Jones #2934 L.C.R.C. L6061, P389

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found 1/2" pipe at base of fence line occupies this corner. Current measurements match 2 ties from L.C.R.C. L6061, P389. Field measurements were obtained between the following corners:

E-9 to F-9	F-9 to G-9
2629.40 meas.	2635.37 meas.
2626.14 Rec. G.L.O.	2626.14 Rec. G.L.O.
2629.57 Rec. calc. from MDOT R-O-W	2637.90 Rec. Plat
Plan 63-R-1 Sheet 19	L 54A P60

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found 1/2" pipe with a concrete monument with brass disk, stamped "Oakland County Remonumentation PS 37281". Witnesses are as follows:

Due North, 32.03' P.K. nail and remon. washer W. face U-pole
 Due North, 15.70' P.K. nail and remon. washer W. face 10" Elm
 Due South, 31.02' P.K. nail and remon. washer E. face 18" Box Elder
 S. 80° E., 10.92' P.K. nail and remon. washer S.W. face Triple 10" Maple
 N. 85° E., 9.51' P.K. nail and remon. washer S. face Triple 8" Maple

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date March 24, 1998



7 JD FILE
2 JD