

LIRFR 17932PG788

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey

T 1-N R 9-E _____ G-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

SURVEY & REMONUMENTATION

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 5-14-97 13
\$ 7.00 MISCELLANEOUS RECORDATION
\$ 2.00 REMONUMENTATION
2 JAN 98 9:04 A.M. RECEIPT # 128

PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

MAR 21 2000

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____ SECTION _____

I, John N. Redash, in a field survey on March 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1816	Set post corner	J.Wampler	n/a	GLO notes
1989	No reference	D. Ross	#19005	Unrecorded survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found monument box at the intersection of Farmington Road and Eleven Mile Road is currently occupying this corner. No L.C.R.C.'s have been recorded as of this date. Field measurements were obtained between the following corners:

F-7 to G-7	G-7 to H-7
2640.50 Meas.	2650.92 Meas.
	2750.94 Rec. Unrecorded Survey D. Ross #19005

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 3/4" iron rod with a 2" diameter brass disk stamped "Oakland County Remonumentation #19005" in the existing monument box. Witness ties are as follows:

S. 45° W.,	89.02'	P.K. nail and remon. tag S.E. face 18" Maple
West,	54.70'	P.K. nail and remon. tag S. face U-pole
N. 25° E.,	70.58'	P.K. nail and remon. tag N.W. face U-pole
S. 45° E.,	84.90'	P.K. nail and remon. tag N.W. face U-pole
West,	15.04'	Found P.K. nail



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
Surveyor's Michigan License No. 37281

Date March 24, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

JA-2 980000750

7.00 FILE
2.00