

LAND-CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Farmington Twp. Corner Code #

- 1. Public Land Survey T 1-N R 9-E G-10
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____ SURVEY & REMONUMENTATION
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

MAR 21 2000

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on March 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 Set post	S. Carpenter	N/A	G.L.O. notes
1960 Not described	Salle Engineering	N/A	Unrecorded Survey #2989
1975 Found iron pipe in concrete pavement	D. Hooth	#7966	L.C.R.C. L6479, P164

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found pipe in monument box in concrete pavement currently occupies this corner. Current measurements match all three ties from L.C.R.C. L6479 P164. Field measurements were made between the following corners:

G-9 to G-10	G-10 to G-11
2648.43 Meas.	2653.63 Meas.
2640.00 Rec. G.L.O.	2640.00 Rec. G.L.O.
2649.75 Rec. Plats L54, P6, L54A, P91 and L54A P60 (Calc)	2654.00 Rec. plats L54, P5 2653.43 Rec. MDOT ROW plan 63-R-1 Sheet #16

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found pipe with a 5/8" x 24" iron rod with 2" dia. brass cap stamped "Oakland County Remonumentation Station P6 #31 P1" in a new monument box. Witness ties are as follows:

N. 45° E.,	49.30'	S.W. Corner brick building.
S. 30° E.,	73.19'	Cut cross N.E. bolt of light pole base
S. 70° W.,	26.84'	P.K. nail and remon. washer S. face U-Pole
N. 40° W.,	24.99'	Cut cross in N.E. bolt of light pole base

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date March 24, 1997
Surveyor's Michigan License No. 37281



Compliance with ACT 345, P.A. 1990
APPROVED ON: 5-19-97 TS
OAKLAND COUNTY REMONUMENTATION
\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REGISTER OF DEEDS STAMP & FILE NUMBER
REMONUMENTATION
2 JAN 98 9:05 A.M. RECEIPT# 12A
PAID RECORDED - OAKLAND COUNTY
LYNN B. ALLEN, CLERK/REGISTER OF DEEDS

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						