

LIBER 17932 PG 795

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Farmington Twp. Corner Code #

- 1. Public Land Survey T 1-N R 9-E H-9
2. Property Controlling in Section S T R SURVEY & REMONUMENTATION
3. Miscellaneous Property in Sec. S T R MAR 21 2000

- 4. Lot No. , Recorded Plat SECTION
5. Private Claims

I, John N. Redash, in a field survey on March 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 Set post S. Carpenter n/a GLO notes
1975 Not described G. Stanley n/a Unrecorded survey
No L.C.R.C.'s have been recorded up to this date

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1" form pin in monument box currently occupies this corner. Concrete monuments were found on the west line of Bel-Aire Hills Subdivision, L72, P26 and used to re-establish this corner. Monument box was found to be 2.60' west of this established corner.

- G-9 to H-9 H-9 to I-9
2627.01 meas. 2636.88 Meas.
2622.51 Rec. G.L.O. 2640.00 Rec. G.L.O.
2624.52 Rec. survey unrecorded 2636.73 Rec. Plats L72, P26
2625.26 Rec. Plats L92, P26 and L40, P24

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 5/8" x 24" iron rod in a new monument box in asphalt pavement 2.60' east of the existing form pin and monument box. Witnesses are as follows:

- N. 38° E., 92.93' P.K. Nail and remon. tag in N.W. face 26" Maple
S. 28° E., 47.95' P.K. Nail and remon. tag in S.W. face U-pole
S. 06° E., 75.08' P.K. Nail and remon. tag in W. face U-pole
N. 30° W., 72.08' P.K. Nail and remon. tag in S.W. face U-pole
S. 68° W., 71.66' P.K. Nail and remon. tag in S.E. face U-pole
Due West 2.55' Found 1" form pin in monument box



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date March 24, 1997

Surveyor's Michigan License No. 37281

Compliance with ACT 345, P.A. 1990
APPROVED ON: 5-19-97 FS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
RECORDATION
2 JAN 98 9:06 A.M. RECEIPT# 12A
PAID B C D RECORDED - OAKLAND COUNTY
LYNN B. ALLEN, CLERK/REGISTER OF DEEDS

JA-298000244

COPY