

LIBER 17932PG798

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Farmington Twp. Corner Code #

1. Public Land Survey T 1-N R 9-E H 13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

SURVEY & REMONUMENTATION
MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 5-19-97 3

OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

JA-2 9800002146

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 JAN 98 9:06 A.M. RECEIPT# 128
 PAID B C D RECORDING G OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

3					
4	7	8	9	10	11
5					
6	18	17	16	15	14
7					
8	19	20	21	22	23
9					
10	30	29	28	27	26
11					
12	31	32	33	34	35
13					

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

I, John N. Redash, in a field survey on March 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 Set post corner J. Wampler n/a GLO notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found 1" pipe in monument box currently occupies this corner. No L.C.R.C.'s or surveys are on record.

G-13 to H-13	H-13 to H-1 (T-1-S., R-9-E.)	H-13 to I-13
2632.97 Meas.	48.18 Meas.	2635.67 meas.
2640.00 Rec. G.L.O.		2640.00 Rec. G.L.O.
2633.30 Rec. Plats L57, P54 & L94, P32		

7.00 FILE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" pipe with a 5/8" x 24" iron rod with 2" diameter brass cap stamped "Oakland County Remonumentation 95#31241". Witnesses are as follows:

N. 30° E., 92.00'	S.W. corner of building
N. 47° W., 98.38'	S.E. corner of building
Due West, 48.18'	Found 1/2" iron in monument box (H-1) (T-1-S., R-9-E.)
S. 60° W., 136.43'	P.K. nail and remon. washer N. face 18" Pine
S. 10° W., 55.81'	P.K. nail and remon. washer E. face light pole



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash

Date March 24, 1997

Surveyor's Michigan License No. 37281