

MAY 22 1997

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 & 7.00 MISCELLANEOUS RECORDING

COMMISSION

For corners in

Oakland  
(County)

Located in: Farmington Corner Code #  
Township

- |                                    |   |           |   |           |            |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>1N</u> | R | <u>9E</u> | <u>1-9</u> |
|                                    | T |           | R |           |            |
|                                    | T |           | R |           |            |
|                                    | T |           | R |           |            |
| 2. Property Controlling in Section | S |           | T |           |            |
|                                    | S |           | T |           |            |
| 3. Miscellaneous Property in Sec.  | S |           | T |           |            |
|                                    | S |           | T |           |            |

\$ 2.00 REMONUMENTATION  
18 DEC 96 1:36 P.M. RECEIPT# 35B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 10-23-96 TS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-9	1817	Wampler	G.L.O.	Set Post
	1942	N/A	Supervisor's Plat of Westhill Woods L. 49 P. 56	N/A
	1958	Cole	Cert Survey	Iron in Monument Box
	1987	Wilkerson	L.C.R.C. L. 10206 P. 762	Iron
	1990	N/A	O.C.R.C. Alignment Plan	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 L.C.R.C. L. 10206 P. 762 appears to be filed in error as no witnesses shown check to this monument box. Liber 20206 P. 762 shows irons 50.12' North and 46.0' South which would lead one to believe that this corner would be in an East-West road only and not the intersection of a North, South, East and West road. Found a 3/8" iron in a monument box in the C/L of 10 Mile Road running East and West 4' West of the C/L of Orchard Lake Road running North and South. O.C.R.C. Alignment Plan shows Section Corner as being 3.74' West of construction C/L of Orchard Lake Road. This corner checks very closely the distance shown to I-10 and J-9 on the Oakland County Road Commission Alignment Plan (1990) and to I-10 shown in Supervisor's Plat of Westhill Woods L. 49 P. 56 (1942).

- Measure North 2639.29' to I-8 (G.L.O. = 2640.0')
- Measure South 2650.62' to I-10 (G.L.O. = 2640.0') (O.C.R.C. = 2650.35') (Sup. Plat Westhill Woods = 2650.4')
- Measure East 2631.58' to J-9 (G.L.O. = 2617.6') (O.C.R.C. = 2631.51')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-9 Replaced the 3/8" iron with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side DE Pole N 38° W 82.54'
  - Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side DE Pole N 56° E 90.21'
  - Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side Guy Pole S 65° E 158.17'
  - Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side Guy Pole S 82° W 164.15'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96

Surveyor's Michigan License No. 25854

