

MAY 22 1997

LIBER 16848 PG 771

COMMISSION

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in

Oakland (County)

Located in: Farmington Corner Code # Township

- 1. Public Land Survey T 1N R 9E I-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

18 DEC 96 1:36 P.M. RECEIPT# 35B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 10-23-96 TS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on September 2, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Date (1817-1990), Name (Wampler, Baldwin, N/A, Stephens, J. Smith), Title (G.L.O., County Surveyor, Supervisor's Plat of Westhill Woods L. 49 P. 56, L.C.R.C. L. 11381 P. 059, Survey), and Monument Type (Set Post, Iron, N/A, PK Nail, Iron Rod).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found a 1/2" rebar 15.2' West of the C/L of Orchard Lake Road running North and South and 4' North of the C/L of Fink Avenue running East per L.C.R.C. L. 11381 P. 059. This corner checks very closely the distance shown to I-9 and I-11 in the Oakland County Road Commission Alignment Plan (1990) and to I-9 in the Supervisor's Westhill Woods Plat L. 49 P. 56 (1942).

L.C.R.C. L. 11381 P. 059 (1989)
N 82° W 118.00' SE Corner Brick Bldg.
N 68° W 142.96' NE Corner Brick Bldg.
N 82° W 45.97' N Side Util. Pole
N 76° E 69.62'S Side Util. Pole

Measure North 2650.62' to I-9 (G.L.O. = 2640.0') (O.C.R.C. = 2650.35') (Sup. Plat Westhill Woods L. 49 P. 56 = 2650.4')
Measure South 2633.09' to I-11 (G.L.O. = 2640.0') (Smith Survey = 2633.1') (O.C.R.C. = 2633.18')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Replaced the 1/2" rebar nail with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854." Also set a new monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side Util. Pole N 82° W 45.97'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side Util. Pole N 76° E 69.62'
Corner Brick Bldg. N 82° W 118.00' SE
NE Corner Brick Bldg. N 68° W 142.97'
C/L Top Hydrant S 48° E 73.61'
C/L Orchard Lake Road N 90° E 15.2'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH
Surveyor's Michigan License No. 25854

