

**SURVEY & REMONUMENTATION**

LIBER **16848 PG 773**

MAY 22 1997

**COMMISSION**

Dec 18 96 305714

**LAND CORNER RECORDATION CERTIFICATE** \$ 7.00 MISCELLANEOUS RECORDING  
 Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

18 DEC 96 1:36 P.M. RECEIPT# 35B  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland  
 (County)

Located in: Farmington Corner Code #  
 Township

- |                                    |   |           |   |           |             |
|------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey              | T | <u>1N</u> | R | <u>9E</u> | <u>I-12</u> |
|                                    | T | _____     | R | _____     | _____       |
|                                    | T | _____     | R | _____     | _____       |
|                                    | T | _____     | R | _____     | _____       |
| 2. Property Controlling in Section | S | _____     | T | _____     | _____       |
|                                    | S | _____     | T | _____     | _____       |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____     | _____       |
|                                    | S | _____     | T | _____     | _____       |

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 10-23-96 TS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
6											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1817	Wampler	G.L.O.	Set Post
	1943	McMahon	Survey	N/A
	1945	N/A	Supervisor's Eight Mile Grand River Acres No. 1 L. 56 P. 40	N/A
	1945	N/A	Supervisor's Eight Mile Grand River Acres No. 2 L. 56 P. 47	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found 1/2" rebar in a monument box on the C/L of Orchard Lake Road running North and South. Also found the following witnesses. No information on record. This corner checks very closely the distance shown to I-11 and I-13 per Supervisor's Eight Mile Grand River Acres No. 1 and No. 2 L. 56 P. 4 and L. 56 P. 47 (1945).

Measure South 2646.20' to I-13 (G.L.O. = 2640.0') (Sup. Eight Mile Grand River Acres No. 1 = 2646.09')  
 Measure North 2671.78' to I-11 (G.L.O. = 2640.0') (Sup. Eight Mile Grand River Acres No. 2 = 2671.86')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Replaced the 1/2" rebar with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side P. Pole N 20° E 149.96'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side P. Pole S 84° W 52.43'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 20" Walnut S 30° W 102.14'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 12" Pine S 38° E 92.54'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole S 54° E 62.57'

7.00 File  
 2.00

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96  
 EARTH TECH  
 Surveyor's Michigan License No. 25854

