

MAY 22 1997 COMMISSION

LIBER 16848 PG 774

Dec 18 96 305715

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

18 DEC 96 1:37 P.M. RECEIPT# 358 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (County)

Located in: Farmington Corner Code # Township

- 1. Public Land Survey T 1N R 9E I-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 10-23-96 TS OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on September 2, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 1817 Wampler G.L.O. Set Post
1945 N/A Supervisor's Eight Mile Grand River Acres No. 1 L. 56 P. 40 N/A

Records indicate this corner is not common with I-1, T1S, R9E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 3/8" iron in a monument box on the southerly extension of the C/L of Orchard Lake Road running North and on the C/L of 8 Mile Road running East and West. 44.2' East of monument box at I-1, T1S, R9E. This corner checks very closely the distance North to I-12 per Supervisor's Eight Mile Grand River Acres No. 1 L. 56 P. 40 (1945).

Measure East 2635.85' to J-13 (G.L.O. = 2640.0')
Measure North 2646.20' to I-12 (G.L.O. = 2640.0') (Supervisor's Eight Mile Grand River Acres No. 1 = 2646.09')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Replaced the 3/8" iron with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole N 50° E 71.08'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole N 54° W 88.36'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole S 62° W 113.74'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side P. Pole S 00° E 140.96'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/16/96
EARTH TECH
Surveyor's Michigan License No. 25854

