

MAY 2-2 1997

LIBER 16848 PG 776

DEC 18 96 305717

LAND CORNER RECORDATION CERTIFICATE § 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 § 2.00 REMONUMENTATION

COMMISSION
For corners in

Oakland
(County)

Located in: Farmington Corner Code #
Township

18 DEC 96 1:37 P.M. RECEIPT# 35B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 10-23-96 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 1N R 9E J-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9	1817	Wampler	G.L.O.	Set Post
	N/A	N/A	L.C.R.C. L. 10206 P. 763	N/A
	1984	Roskelly	Cert. Survey	Iron
	1990	N/A	Oakland County Road Commission Alignment Plan	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found iron in a monument box in the C/L of 10 Mile Road running East and West per L.C.R.C. L. 10206 P. 763. This corner is 1.40' East of the midpoint between I-9 and K-9. Checks distance very closely West to I-9 per Oakland County Road Commission Alignment Plan (1990).

- L.C.R.C. L. 10206 P. 763
- N 07° E 62.29' PK Nail in W Side DE Pole
- N 42° E 84.88' PK Nail in SE Side DE Pole
- S 40° E 42.71' PK Nail in W Side Guy Pole
- S 74° W 99.47' Arrow on Hydrant

Measure East 2628.77' to K-9 (G.L.O. = 2617.6') (Springbrook No. 4 & Barbizon Estates = 2629.5')
Measure West 2631.58' to I-9 (G.L.O. = 2617.6') (O.C.R.C. = 2631.51')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Replaced the iron in a monument box with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side DE Pole N 07° E 62.34'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side DE Pole N 44° E 84.89'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side Guy Pole S 59° E 42.70'
- C/L Extended El Marco N 90° E 169.34'
- Fire Hydrant S 75° W 99.72

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/10/96
EARTH TECH
Surveyor's Michigan License No. 25854

