

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

LIBER 16848 PG 778

Dec 18 96 305719

\$ 7.00 MISCELLANEOUS RECORDING

LAND CORNER RECORDATION CERTIFICATE 2.00 REMONUMENTATION

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 96 1:37 P.M. RECEIPT# 358
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (County)	Located in: Farmington Corner Code # Township
1. Public Land Survey	T <u>1N</u> R <u>9E</u> <u>J-13</u> T _____ R _____ T _____ R _____ T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____

Compliance with ACT 345, P.A. 1990
APPROVED ON: 10-23-96 TS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered; found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13	1817	Wampler	G.L.O.	Set Post
	1917	N/A	Brookside Park Sub. L. 19 P. 4	N/A
	1987	R. Pitts	Survey	N/A
	N/A	N/A	Warner, Cantrell & Padmos Survey	N/A

Records indicate this corner is not common with J1, T1S, R9E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found a 3/8" iron in a monument box at the C/L intersection of 8 Mile Road running East and West and Tuck Road running North as shown in Brookside Park Sub. L. 19 P. 4 and RM Pitts Survey. Found 3/8" iron bar in a monument box (J-1, T1N, R9E) N 90° W 72.55'. This corner faces 2.46' East of the midpoint between I-13 and M-13. Checks closely the distance East to K-13 per Brookside Park Sub. L. 19 P. 4 (1917).

Measure West 2635.85' to I-13 (G.L.O. = 2640.0')
Measure East 2630.94' to K-13 (G.L.O. = 2640.0') (Brookside Park Sub. = 2633.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Replaced the 3/8" iron with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 18" Maple N 41° E 60.73'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side Guy Pole S 52° E 79.25'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side Lt. Pole S 62° W 109.69'
SW Cor. Catch Basin N 62° E 61.25'
NW Cor. Catch Basin S 27° W 32.12'
N 1/2 Cor. Sec. 2 T1S, R9E, Wayne Co. N 90° W 72.55'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH

Surveyor's Michigan License No. 25854

