

MAY 2 2 1997
OAKLAND COUNTY
COMMISSION

LAND CORNER RECORDATION CERTIFICATES 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in

Oakland
(County)

Located in: Farmington Corner Code #
Township

- 1. Public Land Survey T 1N R 9E L-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

18 DEC 96 1:39 P.M. RECEIPT# 358
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 10-29-96 TS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1817	Wampler	G.L.O.	Set Post
	1852	NA	Survey	N/A
	1890	Russell	County Survey	N/A
	1936	Baldwin	County Survey Notes	Bronze Monument
	1939	Knight	Unrecorded Plat/Noble Brook Farms	Monument
	1972	Postiff	Recorded Survey L. 6905 P. 110	N/A
	1986	Roskelly	Cert. Survey	N/A
	1994	Roskelly	L.C.R.C. L. 14687 P. 803	Mon. Box w/Bronze Disc
	1994	N/A	Arbor Oaks Sub. L. 233 P. 1-3	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found a brass disc in a monument box on the C/L of 9 Mile Road running East and West at Averhill running South per L.C.R.C. L. 14687 P. 803 which checks the description of a bronze monument shown in the 1936 Baldwin survey. This corner falls 1.03' West of the midpoint between K-11 and M-11 and is approximately 0.4' South of a straight line between said corners. Also checks closely the distance to M-11 per Arbor Oaks Sub. L. 233 P. 1-3 (1994).

L.C.R.C. L. 14687 P. 803 (1994)

- Tag GLA #28400 in guy pole N. 50° E. 41.65'
- Tag GLA #28400 in utility pole S. 30° E. 40.03'
- Tag GLA #28400 in 12" pine tree S. 50° W. 69.12'
- Tag GLA #28400 in 36" oak tree N. 20° W. 30.96'

Measure East 2633.24' to M-11 (G.L.O. = 2624.5') (Arbor Oaks Sub. = 2633.66')
Measure West 2631.68' to K-11 (G.L.O. = 2624.5')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Replaced the brass disc with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side Guy Pole N 49° E 41.65'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side Util. Pole S 36° E 40.05'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 14" Pine S 46° W 69.11'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 36" Maple N 18° W 31.05'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH
Surveyor's Michigan License No. 25854

