



LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
18 DEC 96 1:39 P.M. RECEIPT# 35B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (County)	Located in: Farmington Corner Code # Township	
1. Public Land Survey	T <u>1N</u> R <u>9E</u> <u>L-13</u>	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 10-29-96 TS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 1817 Wampler G.L.O. Set Post
1890 Russell County Surveyor N/A
1980 Parish L.C.R.C. L. 7839 P. 523 Concrete Monument in a Monument Box

Records indicate this corner is not common with L-1, T1S, R9E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found a concrete monument in a monument box at the C/L intersection of 8 Mile Road running East and West and Pearl Street running North per L.C.R.C. L. 7839 P. 523. This corner falls 2.03' West of the midpoint between K-13 and M-13.

L.C.R.C. L. 7839 P. 523 (1980)
N 45° E 58.75' SW Corner CB Rim
S 45° E 42.60' NW Corner CB Rim
South 30.5' Back of Conc. Curb
West 45.41' C/L Mon. Box (N 1/4 Sec. 1, T1S, R9E)
N 45° W 48.50' Tag #340 SW Face Util. Pole
Measure East 2631.32' to M-13 (G.L.O. = 2640.0')
Measure West 2627.26' to K-13 (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Set a brass cap stamped "Oakland County Remonumentation P.S. #25854" on the existing concrete monument in a monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole N 32° W 48.55'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side P. Pole N 76° E 148.01'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole S 71° E 148.86'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 28' Willow S 25° W 82.49'
SW Corner Catch Basin N 61° E 58.94'
NW Corner Catch Basin S 48° E 42.76'
Back of Curb S 00° E 30.6'
N 1/4 Sec. 1, T1S, R9E S 90° W 45.49'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH
Surveyor's Michigan License No. 25854

